

Landscape Works Site-Readiness Checklist

Mother Earth Gardens · prepare your site before planting starts

Landscape installation runs faster and cleaner when the site is ready before the crew arrives. Use this checklist to prepare the area ahead of mobilization — an unready site is the most common cause of avoidable delay and standby cost.

Access & area

- Work area is cleared of construction debris, spoil, and stored materials
- Delivery access for trucks and plant material is open and passable
- The landscape area is handed over / demarcated so scope boundaries are clear
- Any demolition or earthworks in the area are complete

Below-grade & structure

- Waterproofing on planters and podium decks is complete and flood-tested (documented)
- Drainage outlets / weep holes are in place and unobstructed
- Underground utilities in the planting zone are marked or confirmed clear
- Structural slab loading has been confirmed for the specified soil depth and plant sizes

Levels, soil & services

- Finished grade levels are set so soil buildup reaches correct depth
- A water source is available on site for planting and establishment
- Power is available if lighting or irrigation controllers are in scope
- Any hardscape the planting depends on (edging, walls, kerbs) is in place

Coordination

- Site contact and reporting line are agreed before mobilization
- Working hours and any occupied-site sequencing constraints are confirmed
- Storage / laydown area for delivered plants is identified

Mother Earth Gardens · meglandscaping.com · inquiry@meglandscaping.com · +63 928 551 0587. Hand this to your GC or site team before landscape mobilization. Questions on any item? Get in touch.